



NOTES:

- ① PROVIDE 1/2" EXP. JT.
- ② PROVIDE 1/2" EXP. JTS. WHERE WALK ABUTS BUILDING WALLS AND RETAINING WALLS.
- ③ PROVIDE 1/2" EXP. JTS. AT PROPERTY LINE AND 100 FT. MAXIMUM INTERVALS.
- ④ SEE PLATE NO. 3-02 FOR CONCRETE SILL DETAIL.
- ⑤ CONTRACTION JOINT SPACING SHOULD BE 1.5 "D" OR 12' WHICHEVER IS LESS.
- ⑥ SEE CITY OF RED WING PEDESTRIAN CURB RAMP STANDARD PLANS FOR RAMP DETAILS.
- ⑦ SIDEWALK THICKNESS IS 6" THRU DRIVE WITH 6" CL.5 BASE.
- ⑧ SEE PLATE NOS. 3-05 & 3-06 FOR CONCRETE DRIVE APPROACH DETAILS.
- ⑨ LONGITUDINAL JOINTS REQUIRED WHEN "D"=8' OR GREATER.
- ⑩ CONCRETE - MnDOT SPEC. MIX 3F52.
- 11. CONCRETE TO BE CONSTRUCTED ON PROPERLY COMPACTED BASE.

DATE REVISED  
04/26/17

**SIDEWALK DETAILS**

PLATE NO.  
3-10