



CITY COUNCIL MEETING STAFF REPORT

To: City Council Members and Mayor
From: Jerry Plein
Meeting Date: February 13, 2023
Agenda Item Number: 10.A.

Title Consider Motion to Approve Actions Relating to the Neal Street Ravine Stabilization Project.

As part of the City of Red Wing Surface Water Management Plan, SEH developed a design to stabilize the Neal Street Ravine. The ravine has been experiencing severe erosion that has become significantly more extensive over the past few years. Sediment is discharged directly to the downstream storm sewer system, which discharges into Hay Creek. The 2022 CIP includes \$850,000 for the repair of the ravine. Staff is requesting authorization to advertise for bids for the stabilization project as well as authorization to apply for a grant for up to \$10,000 from Zumbro Watershed Alliance.

1. Accept Plans for the Neal Street Ravine Stabilization Project.
2. Authorize Staff to Advertise for Bidders for the Project.
3. Authorize Staff to Apply for Grant Funding from the Zumbro Watershed Alliance for up to \$10,000.

Purpose

Motion to Approve Actions Relating to the Neal Street Ravine Stabilization Project.

Recommended Action Consider Motion to Approve Actions Relating to the Neal Street Ravine Stabilization Project.

As part of the City of Red Wing Surface Water Management Plan, SEH developed a design to stabilize the Neal Street Ravine. The ravine has been experiencing severe erosion that has become significantly more extensive over the past few years. Sediment is discharged directly to the downstream storm sewer system, which discharges into Hay Creek. The 2022 CIP includes \$850,000 for the repair of the ravine. Staff is requesting authorization to advertise for bids for the stabilization project as well as authorization to apply for a grant for up to \$10,000 from Zumbro Watershed Alliance.

1. Accept Plans for the Neal Street Ravine Stabilization Project.
2. Authorize Staff to Advertise for Bidders for the Project.
3. Authorize Staff to Apply for Grant Funding from the Zumbro Watershed Alliance for up to \$10,000.

Attachments

1. 02-08-2023 PLANS

Strategic Plan Alignment

This project is in alignment with strategy #49 to maintain, upgrade, and rehab current storm water ponds and #51 to fix erosion problems in large ravines.

Background

Hay Creek is a MnDNR designated trout stream that runs south to north to the Mississippi River. The stream runs through the City limits, west of the downtown area. The Neal Street ravine is a tributary to Hay Creek. This approximate 2,000-foot ravine runs parallel to Siewert Street on the West and extends from Neal Street to Featherstone Road. The drainage from the ravine is conveyed to Hay Creek by the storm sewer under Featherstone Road.

The ravine has been experiencing severe erosion that has become significantly more extensive over the past few years. Sediment is discharged directly to the downstream storm sewer system, which discharges to Hay Creek. Several options have been investigated in the past; however, nothing has been implemented.

In March 2022, Staff entered into a professional services agreement with SEH for \$64,900 to perform the engineering analysis, design and construction administration services for the project. The plans are complete, and staff is requesting Council to accept the plans.

On October 24, 2022, Council approved the purchase of parcels 55.590.0960 and 55.590.0990 from Siewert Construction to facilitate the needed repairs to the Neal Street Ravine.

Discussion

Staff have been aware of some erosion problems on the property between the Woodland Hills addition and Kull addition. The naturally forested ravine conveys stormwater runoff from a large residential area, and the steep banks have significantly eroded. This project has been identified in the Surface Water Management Plan (SWMP) which was completed in 2014 as well as the SWMP amendment which was adopted by Council in June of 2022. The eroding area drains a large sediment load directly into Hay Creek, making the repairs a priority for Public Works. Hay Creek is a freshwater trout stream that drains into the Mississippi River, which is listed as an impaired water for turbidity.

Preliminary survey data was collected to capture the existing ravine profile and cross-sectional data. This survey data was used to create a digital elevation model (DEM) and the ravine area of the Hay Creek model was converted from 1D to 2D within the model to get a better idea of how water flows within the ravine. This also allowed the visualization of flow depths and localized high velocity zones.

A site visit was performed on July 23, 2021, to evaluate erosion areas in the ravine. Significant erosion was observed within the ravine. The erosion has resulted in nearly vertical channel banks ranging from three feet to twelve feet high. Near the bottom where the grade significantly flattens out, a sediment delta has formed.

Staff is requesting Council approval to advertise for bidders for the project. When bids are

received, staff will return to Council to present the results and request direction on how to proceed. Engineers' estimates are typically conservative, so staff is hopeful that the bids will be favorable for the overall budget. The successful bidder will have options on how to construct the project.

The major requirement is the building of the pond at the bottom of the ravine, which will need to be constructed first to enable a settling area for any material that may erode during construction. They will be required to clean out the debris to the designed standard when finished. The anticipated construction sequence would be working from the bottom of the ravine towards the top end of the ravine. Soil corrections will take place as they work up the ravine and it is expected that there will no need to haul in extra fill or remove additional fill. If this is required, the city has excess fill available for the project. Once the soil corrections have taken place and the access road has been constructed, the contractor will work back down the newly graded ravine with geotextile fabric and rip rap while tying in drainage from residents as they go, as well as repairing some damaged storm drains that dump into the ravine. Once finished, the base of the ravine will be rip rap from the top down with an access road for future repairs located next to it. There will be a shallow pond/settling area at the bottom that will have access points for the city to clean out as needed in the future.

Other than noise during the construction, the neighboring properties will not be affected by the project. The main benefit to affected properties will be that the erosion of their property into the ravine will be corrected. If we are successful in securing the grant for the rain barrels, this will further help contain run-off from the residential houses on the project. Staff has been in contact with the Watershed Alliance for the Greater Zumbro River (WAGZ) as a possible funding source for Rain Barrel acquisition for the affected neighbors. This funding is made available through the One Watershed, One Plan program that supports local partnerships for watershed actions, which includes the Hay Creek Watershed in Red Wing. The workplan includes actions to support a cost share project for residential stormwater management practices. We anticipate doing some educational training with a master gardener and offering that advice and expertise to the affected properties along with the rain barrels to eliminate or greatly reduce the amount of run-off from each residence. If the grant is successful, we anticipate holding a neighborhood meeting with the affected residents and offering the rain barrels and general education on how to utilize the barrels to reduce runoff into the ravine.

This project has been in discussion for a considerable period of time with multiple conversations on whether the owners of the parcels within the project should be responsible for the repairs. With much discussion and previous City Council approval, it was determined that the drainage area is quite large and beyond what is just received from the adjacent properties. The city collects a large portion of the drainage area in the pond on the corner of Seiwert and Neal Streets to slow down the discharge into this ravine. That pond has worked well but it does not correct the downstream issues from the discharge point of the pond.

Financial Plan and ImpactThe Stormwater Fund has allocated \$850,000 in the 2023 CIP. Utility and Finance staff have been working with SEH to secure outside funding sources for this project and have found no alternative funding available. Staff has been in contact with the Watershed Alliance for the Greater Zumbro River (WAGZ) for possible funding for Rain Barrel acquisition for affected neighbors of the project. This funding is made available through the One Watershed, One Plan program that supports local partnerships for watershed actions,

which includes the Hay Creek Watershed in Red Wing with \$10,000 allocated for 2023. Not included in this project estimate is the purchase of the 2 parcels that are needed for construction. The Council previously approved the purchase of 2 parcels for \$45,702 which can be partially or fully funded out of the 652-stormwater operations budget.

Item Description	Total Cost
Construction Activities	\$185,180
Materials	\$424,310
Soil Stabilization	\$ 58,131
Sub-total	\$667,621
Design (SEH)	\$64,900
Construction Inspection and oversight	\$66,762
Contingency - 10%	\$66,762
Total	\$866,045





Alternatives

1. Accept Plans for the Neal Street Ravine Stabilization Project.
2. Authorize Staff to Advertise for Bidders for the Project.
3. Authorize Staff to Apply for Grant Funding from the Zumbro Watershed Alliance for up to \$10,000.
4. Reject Staff recommendation and direct staff to consider other options.

Recommended Action Consider Motion to Approve Actions Relating to the Neal Street Ravine Stabilization Project.

As part of the City of Red Wing Surface Water Management Plan, SEH developed a design to stabilize the Neal Street Ravine. The ravine has been experiencing severe erosion that has become significantly more extensive over the past few years. Sediment is discharged directly to the downstream storm sewer system, which discharges into Hay Creek. The 2022 CIP includes \$850,000 for the repair of the ravine. Staff is requesting authorization to advertise for bids for the stabilization project as well as authorization to apply for a grant for up to \$10,000 from Zumbro Watershed Alliance.

1. Accept Plans for the Neal Street Ravine Stabilization Project.
2. Authorize Staff to Advertise for Bidders for the Project.
3. Authorize Staff to Apply for Grant Funding from the Zumbro Watershed Alliance for up to \$10,000.







BIOROLL DITCH CHECK
 Rev'd Oct 2011
 SHEP # ERO-05

BIOROLL BLANKET SYSTEM
 Rev'd Oct 2011
 SHEP # ERO-06

BIOROLL STAKING
 Rev'd Oct 2011
 SHEP # ERO-07

EROSION CONTROL BLANKET INSTALLATION
 Rev'd Oct 2011
 SHEP # ERO-11



BLANKET STAPLING PATTERN (PLATE 1 OF 2)
 Rev'd Oct 2011
 SHEP # ERO-12



BLANKET STAPLING PATTERN (PLATE 2 OF 2)
 Rev'd Oct 2011
 SHEP # ERO-12

SILT FENCE
 Rev'd Jan 2013
 SHEP # ERO-15


CLASS II AND III RIPRAP AT OUTLETS
 Rev'd Oct 2011
 SHEP # ERO-23

SEH Project	107247	Rev#	Revision Issue Description	Date	Rev#	Revision Issue Description	Date	SEH Project	107247	Rev#	Revision Issue Description	Date	Rev#	Revision Issue Description	Date
Drawn By	RP							SEH Project	107247	Rev#	Revision Issue Description	Date	Rev#	Revision Issue Description	Date
Designed By	HS							SEH Project	107247	Rev#	Revision Issue Description	Date	Rev#	Revision Issue Description	Date
Checked By	JW							SEH Project	107247	Rev#	Revision Issue Description	Date	Rev#	Revision Issue Description	Date

NEAL STREET RAVINE STABILIZATION
 RED WING, MINNESOTA



NEAL STREET RAVINE



REMOVE AND REPLACE 8 LF 15" RC PIPE AND 1 EA 15" RC APRON 1 EA CONNECT TO EXISTING PIPE. 10 CY OF FILL TO BE PLACED OVER THE NEW PIPE. 20 SY OF GEOTEXTILE FABRIC AND 6 CY OF CL III RANDOM RIPRAP SHALL BE PLACED AT THE END OF THE APRON (SEE RIPRAP AT OUTLET DETAIL)

Rev#	Date	Description
1	7/26/23	ISSUED FOR PERMIT
2	8/15/23	REVISED PER COMMENTS
3	8/22/23	REVISED PER COMMENTS
4	9/12/23	REVISED PER COMMENTS
5	9/20/23	REVISED PER COMMENTS
6	10/10/23	REVISED PER COMMENTS
7	10/17/23	REVISED PER COMMENTS
8	10/24/23	REVISED PER COMMENTS
9	11/01/23	REVISED PER COMMENTS
10	11/08/23	REVISED PER COMMENTS
11	11/15/23	REVISED PER COMMENTS
12	11/22/23	REVISED PER COMMENTS
13	11/29/23	REVISED PER COMMENTS
14	12/06/23	REVISED PER COMMENTS
15	12/13/23	REVISED PER COMMENTS
16	12/20/23	REVISED PER COMMENTS
17	12/27/23	REVISED PER COMMENTS
18	1/03/24	REVISED PER COMMENTS
19	1/10/24	REVISED PER COMMENTS
20	1/17/24	REVISED PER COMMENTS
21	1/24/24	REVISED PER COMMENTS
22	1/31/24	REVISED PER COMMENTS
23	2/07/24	REVISED PER COMMENTS
24	2/14/24	REVISED PER COMMENTS
25	2/21/24	REVISED PER COMMENTS
26	2/28/24	REVISED PER COMMENTS
27	3/06/24	REVISED PER COMMENTS
28	3/13/24	REVISED PER COMMENTS
29	3/20/24	REVISED PER COMMENTS
30	3/27/24	REVISED PER COMMENTS
31	4/03/24	REVISED PER COMMENTS
32	4/10/24	REVISED PER COMMENTS
33	4/17/24	REVISED PER COMMENTS
34	4/24/24	REVISED PER COMMENTS
35	5/01/24	REVISED PER COMMENTS
36	5/08/24	REVISED PER COMMENTS
37	5/15/24	REVISED PER COMMENTS
38	5/22/24	REVISED PER COMMENTS
39	5/29/24	REVISED PER COMMENTS
40	6/05/24	REVISED PER COMMENTS
41	6/12/24	REVISED PER COMMENTS
42	6/19/24	REVISED PER COMMENTS
43	6/26/24	REVISED PER COMMENTS
44	7/03/24	REVISED PER COMMENTS
45	7/10/24	REVISED PER COMMENTS
46	7/17/24	REVISED PER COMMENTS
47	7/24/24	REVISED PER COMMENTS
48	7/31/24	REVISED PER COMMENTS
49	8/07/24	REVISED PER COMMENTS
50	8/14/24	REVISED PER COMMENTS
51	8/21/24	REVISED PER COMMENTS
52	8/28/24	REVISED PER COMMENTS
53	9/04/24	REVISED PER COMMENTS
54	9/11/24	REVISED PER COMMENTS
55	9/18/24	REVISED PER COMMENTS
56	9/25/24	REVISED PER COMMENTS
57	10/02/24	REVISED PER COMMENTS
58	10/09/24	REVISED PER COMMENTS
59	10/16/24	REVISED PER COMMENTS
60	10/23/24	REVISED PER COMMENTS
61	10/30/24	REVISED PER COMMENTS
62	11/06/24	REVISED PER COMMENTS
63	11/13/24	REVISED PER COMMENTS
64	11/20/24	REVISED PER COMMENTS
65	11/27/24	REVISED PER COMMENTS
66	12/04/24	REVISED PER COMMENTS
67	12/11/24	REVISED PER COMMENTS
68	12/18/24	REVISED PER COMMENTS
69	12/25/24	REVISED PER COMMENTS
70	1/01/25	REVISED PER COMMENTS
71	1/08/25	REVISED PER COMMENTS
72	1/15/25	REVISED PER COMMENTS
73	1/22/25	REVISED PER COMMENTS
74	1/29/25	REVISED PER COMMENTS
75	2/05/25	REVISED PER COMMENTS
76	2/12/25	REVISED PER COMMENTS
77	2/19/25	REVISED PER COMMENTS
78	2/26/25	REVISED PER COMMENTS
79	3/05/25	REVISED PER COMMENTS
80	3/12/25	REVISED PER COMMENTS
81	3/19/25	REVISED PER COMMENTS
82	3/26/25	REVISED PER COMMENTS
83	4/02/25	REVISED PER COMMENTS
84	4/09/25	REVISED PER COMMENTS
85	4/16/25	REVISED PER COMMENTS
86	4/23/25	REVISED PER COMMENTS
87	4/30/25	REVISED PER COMMENTS
88	5/07/25	REVISED PER COMMENTS
89	5/14/25	REVISED PER COMMENTS
90	5/21/25	REVISED PER COMMENTS
91	5/28/25	REVISED PER COMMENTS
92	6/04/25	REVISED PER COMMENTS
93	6/11/25	REVISED PER COMMENTS
94	6/18/25	REVISED PER COMMENTS
95	6/25/25	REVISED PER COMMENTS
96	7/02/25	REVISED PER COMMENTS
97	7/09/25	REVISED PER COMMENTS
98	7/16/25	REVISED PER COMMENTS
99	7/23/25	REVISED PER COMMENTS
100	7/30/25	REVISED PER COMMENTS
101	8/06/25	REVISED PER COMMENTS
102	8/13/25	REVISED PER COMMENTS
103	8/20/25	REVISED PER COMMENTS
104	8/27/25	REVISED PER COMMENTS
105	9/03/25	REVISED PER COMMENTS
106	9/10/25	REVISED PER COMMENTS
107	9/17/25	REVISED PER COMMENTS
108	9/24/25	REVISED PER COMMENTS
109	10/01/25	REVISED PER COMMENTS
110	10/08/25	REVISED PER COMMENTS
111	10/15/25	REVISED PER COMMENTS
112	10/22/25	REVISED PER COMMENTS
113	10/29/25	REVISED PER COMMENTS
114	11/05/25	REVISED PER COMMENTS
115	11/12/25	REVISED PER COMMENTS
116	11/19/25	REVISED PER COMMENTS
117	11/26/25	REVISED PER COMMENTS
118	12/03/25	REVISED PER COMMENTS
119	12/10/25	REVISED PER COMMENTS
120	12/17/25	REVISED PER COMMENTS
121	12/24/25	REVISED PER COMMENTS
122	1/01/26	REVISED PER COMMENTS
123	1/08/26	REVISED PER COMMENTS
124	1/15/26	REVISED PER COMMENTS
125	1/22/26	REVISED PER COMMENTS
126	1/29/26	REVISED PER COMMENTS
127	2/05/26	REVISED PER COMMENTS
128	2/12/26	REVISED PER COMMENTS
129	2/19/26	REVISED PER COMMENTS
130	2/26/26	REVISED PER COMMENTS
131	3/05/26	REVISED PER COMMENTS
132	3/12/26	REVISED PER COMMENTS
133	3/19/26	REVISED PER COMMENTS
134	3/26/26	REVISED PER COMMENTS
135	4/02/26	REVISED PER COMMENTS
136	4/09/26	REVISED PER COMMENTS
137	4/16/26	REVISED PER COMMENTS
138	4/23/26	REVISED PER COMMENTS
139	4/30/26	REVISED PER COMMENTS
140	5/07/26	REVISED PER COMMENTS
141	5/14/26	REVISED PER COMMENTS
142	5/21/26	REVISED PER COMMENTS
143	5/28/26	REVISED PER COMMENTS
144	6/04/26	REVISED PER COMMENTS
145	6/11/26	REVISED PER COMMENTS
146	6/18/26	REVISED PER COMMENTS
147	6/25/26	REVISED PER COMMENTS
148	7/02/26	REVISED PER COMMENTS
149	7/09/26	REVISED PER COMMENTS
150	7/16/26	REVISED PER COMMENTS
151	7/23/26	REVISED PER COMMENTS
152	7/30/26	REVISED PER COMMENTS
153	8/06/26	REVISED PER COMMENTS
154	8/13/26	REVISED PER COMMENTS
155	8/20/26	REVISED PER COMMENTS
156	8/27/26	REVISED PER COMMENTS
157	9/03/26	REVISED PER COMMENTS
158	9/10/26	REVISED PER COMMENTS
159	9/17/26	REVISED PER COMMENTS
160	9/24/26	REVISED PER COMMENTS
161	10/01/26	REVISED PER COMMENTS
162	10/08/26	REVISED PER COMMENTS
163	10/15/26	REVISED PER COMMENTS
164	10/22/26	REVISED PER COMMENTS
165	10/29/26	REVISED PER COMMENTS
166	11/05/26	REVISED PER COMMENTS
167	11/12/26	REVISED PER COMMENTS
168	11/19/26	REVISED PER COMMENTS
169	11/26/26	REVISED PER COMMENTS
170	12/03/26	REVISED PER COMMENTS
171	12/10/26	REVISED PER COMMENTS
172	12/17/26	REVISED PER COMMENTS
173	12/24/26	REVISED PER COMMENTS
174	1/01/27	REVISED PER COMMENTS
175	1/08/27	REVISED PER COMMENTS
176	1/15/27	REVISED PER COMMENTS
177	1/22/27	REVISED PER COMMENTS
178	1/29/27	REVISED PER COMMENTS
179	2/05/27	REVISED PER COMMENTS
180	2/12/27	REVISED PER COMMENTS
181	2/19/27	REVISED PER COMMENTS
182	2/26/27	REVISED PER COMMENTS
183	3/05/27	REVISED PER COMMENTS
184	3/12/27	REVISED PER COMMENTS
185	3/19/27	REVISED PER COMMENTS
186	3/26/27	REVISED PER COMMENTS
187	4/02/27	REVISED PER COMMENTS
188	4/09/27	REVISED PER COMMENTS
189	4/16/27	REVISED PER COMMENTS
190	4/23/27	REVISED PER COMMENTS
191	4/30/27	REVISED PER COMMENTS
192	5/07/27	REVISED PER COMMENTS
193	5/14/27	REVISED PER COMMENTS
194	5/21/27	REVISED PER COMMENTS
195	5/28/27	REVISED PER COMMENTS
196	6/04/27	REVISED PER COMMENTS
197	6/11/27	REVISED PER COMMENTS
198	6/18/27	REVISED PER COMMENTS
199	6/25/27	REVISED PER COMMENTS
200	7/02/27	REVISED PER COMMENTS
201	7/09/27	REVISED PER COMMENTS
202	7/16/27	REVISED PER COMMENTS
203	7/23/27	REVISED PER COMMENTS
204	7/30/27	REVISED PER COMMENTS
205	8/06/27	REVISED PER COMMENTS
206	8/13/27	REVISED PER COMMENTS
207	8/20/27	REVISED PER COMMENTS
208	8/27/27	REVISED PER COMMENTS
209	9/03/27	REVISED PER COMMENTS
210	9/10/27	REVISED PER COMMENTS
211	9/17/27	REVISED PER COMMENTS
212	9/24/27	REVISED PER COMMENTS
213	10/01/27	REVISED PER COMMENTS
214	10/08/27	REVISED PER COMMENTS
215	10/15/27	REVISED PER COMMENTS
216	10/22/27	REVISED PER COMMENTS
217	10/29/27	REVISED PER COMMENTS
218	11/05/27	REVISED PER COMMENTS
219	11/12/27	REVISED PER COMMENTS
220	11/19/27	REVISED PER COMMENTS
221	11/26/27	REVISED PER COMMENTS
222	12/03/27	REVISED PER COMMENTS
223	12/10/27	REVISED PER COMMENTS
224	12/17/27	REVISED PER COMMENTS
225	12/24/27	REVISED PER COMMENTS
226	1/01/28	REVISED PER COMMENTS
227	1/08/28	REVISED PER COMMENTS
228	1/15/28	REVISED PER COMMENTS
229	1/22/28	REVISED PER COMMENTS
230	1/29/28	REVISED PER COMMENTS
231	2/05/28	REVISED PER COMMENTS
232	2/12/28	REVISED PER COMMENTS
233	2/19/28	REVISED PER COMMENTS
234	2/26/28	REVISED PER COMMENTS
235	3/05/28	REVISED PER COMMENTS
236	3/12/28	REVISED PER COMMENTS
237	3/19/28	REVISED PER COMMENTS
238	3/26/28	REVISED PER COMMENTS
239	4/02/28	REVISED PER COMMENTS
240	4/09/28	REVISED PER COMMENTS
241	4/16/28	REVISED PER COMMENTS
242	4/23/28	REVISED PER COMMENTS
243	4/30/28	REVISED PER COMMENTS
244	5/07/28	REVISED PER COMMENTS
245	5/14/28	REVISED PER COMMENTS
246	5/21/28	REVISED PER COMMENTS
247	5/28/28	REVISED PER COMMENTS
248	6/04/28	REVISED PER COMMENTS
249	6/11/28	REVISED PER COMMENTS
250	6/18/28	REVISED PER COMMENTS
251	6/25/28	REVISED PER COMMENTS
252	7/02/28	REVISED PER COMMENTS
253	7/09/28	REVISED PER COMMENTS
254	7/16/28	REVISED PER COMMENTS
255	7/23/28	REVISED PER COMMENTS
256	7/30/28	REVISED PER COMMENTS
257	8/06/28	REVISED PER COMMENTS
258	8/13/28	REVISED PER COMMENTS
259	8/20/28	REVISED PER COMMENTS
260	8/27/28	REVISED PER COMMENTS
261	9/03/28	REVISED PER COMMENTS
262	9/10/28	REVISED PER COMMENTS
263	9/17/28	REVISED PER COMMENTS
264	9/24/28	REVISED PER COMMENTS
265	10/01/28	REVISED PER COMMENTS
266	10/08/28	REVISED PER COMMENTS
267	10/15/28	REVISED PER COMMENTS
268	10/22/28	REVISED PER COMMENTS
269	10/29/28	REVISED PER COMMENTS
270	11/05/28	REVISED PER COMMENTS
271	11/12/28	REVISED PER COMMENTS
272	11/19/28	REVISED PER COMMENTS
273	11/26/28	REVISED PER COMMENTS
274	12/03/28	REVISED PER COMMENTS
275	12/10/28	REVISED PER COMMENTS
276	12/17/28	REVISED PER COMMENTS
277	12/24/28	REVISED PER COMMENTS
278	1/01/29	REVISED PER COMMENTS
279	1/08/29	REVISED PER COMMENTS
280	1/15/29	REVISED PER COMMENTS
281	1/22/29	REVISED PER COMMENTS
282	1/29/29	REVISED PER COMMENTS
283	2/05/29	REVISED PER COMMENTS
284	2/12/29	REVISED PER COMMENTS
285	2/19/29	REVISED PER COMMENTS
286	2/26/29	REVISED PER COMMENTS
287	3/05/29	REVISED PER COMMENTS
288	3/12/29	REVISED PER COMMENTS
289	3/19/29	REVISED PER COMMENTS
290	3/26/29	REVISED PER COMMENTS
291	4/02/29	REVISED PER COMMENTS
292	4/09/29	REVISED PER COMMENTS
293	4/16/29	REVISED PER COMMENTS
294	4/23/29	REVISED PER COMMENTS
295	4/30/29	REVISED PER COMMENTS
296	5/07/29	REVISED PER COMMENTS
297	5/14/29	REVISED PER COMMENTS
298	5/21/29	REVISED PER COMMENTS
299	5/28/29	REVISED PER COMMENTS
300	6/04/29	REVISED PER COMMENTS
301	6/11/29	REVISED PER COMMENTS
302	6/18/29	

EROSION PREVENTION MEASURES AND TIMING

THE CONTRACTOR IS RESPONSIBLE FOR ALL EROSION PREVENTION MEASURES FOR THE PROJECT

EROSION PREVENTION MEASURES SHOWN ON PLANS ARE THE ABSOLUTE MINIMUM REQUIREMENTS. THE CONTRACTOR SHALL IMPLEMENT ADDITIONAL EROSION PREVENTION MEASURES AS NECESSARY TO PROPERLY MANAGE THE PROJECT AREA.

THE CONTRACTOR SHALL PLAN AND IMPLEMENT APPROPRIATE CONSTRUCTION PRACTICES AND CONSTRUCTION PHASING TO MINIMIZE EROSION AND RETAIN VEGETATION WHENEVER POSSIBLE.

THE PERMITTEE SHALL DELINEATE AREAS NOT TO BE DISTURBED. PERMITTEE(S) MUST MINIMIZE THE NEED FOR DISTURBANCE OF PORTIONS OF THE PROJECT WITH STEEP SLOPES. WHEN STEEP SLOPES MUST BE DISTURBED, PERMITTEES MUST USE TECHNIQUES SUCH AS PHASING AND STABILIZATION PRACTICES DESIGNED FOR STEEP SLOPES.

THE CONTRACTOR SHALL STABILIZE OF ALL EXPOSED SOILS IMMEDIATELY TO LIMIT SOIL EROSION. IN NO CASE SHALL ANY EXPOSED AREAS, INCLUDING STOCK PILES, HAVE EXPOSED SOILS FOR MORE THAN 14 DAYS WITHOUT PROMOVING TEMPORARY OR PERMANENT STABILIZATION. STABILIZATION MUST BE COMPLETED WITHIN 14 DAYS AFTER CONSTRUCTION ACTIVITY HAS CEASED. TEMPORARY STOCKPILES WITHOUT SIGNIFICANT CLAY, SILT, OR ORGANIC COMPONENTS DO NOT REQUIRE STABILIZATION.

DRAINAGE PATHS, DITCHES, AND/OR SWALES SHALL HAVE TEMPORARY OR PERMANENT STABILIZATION WITHIN 24 HOURS OF CONNECTING TO A SURFACE WATER OR 24 HOURS AFTER CONSTRUCTION ACTIVITY IN THE DITCH/SWALE HAS TEMPORARILY OR PERMANENTLY CEASED.

THE CONTRACTOR SHALL COMPLETE THE STABILIZATION OF ALL EXPOSED SOILS WITHIN 24 HOURS THAT LIE WITHIN 200 FEET OF PUBLIC WATERS PROMULGATED "WORK IN WATER RESTRICTIONS" BY THE MN DNR DURING SPECIFIED FISH SPawning TIMES.

THE CONTRACTOR SHALL IMPLEMENT EROSION CONTROL BMPs AND VELOCITY DISSIPATION DEVICES ALONG CONSTRUCTED STORMWATER CONVEYANCE CHANNELS AND OUTLETS.

THE CONTRACTOR SHALL STABILIZE TEMPORARY AND/OR PERMANENT DRAINAGE DITCHES OR SWALES WITHIN 200 LINEAL FEET FROM PROPERTY EDGE, OR DISCHARGE POINT(S) WITHIN 24 HOURS AFTER CONNECTING TO A SURFACE WATER OR PROPERTY EDGE.

TEMPORARY OR PERMANENT DITCHES OR SWALES USED AS A SEDIMENT CONTAINMENT SYSTEM DURING CONSTRUCTION MUST BE STABILIZED WITHIN 24 HOURS AFTER NO LONGER BEING USED AS A SEDIMENT CONTAINMENT SYSTEM.

THE CONTRACTOR SHALL NOT UTILIZE HYDROMULCH, TACKIFIER, POLYACRYLAMIDE OR SIMILAR EROSION PREVENTION PRACTICES AS A FORM OF STABILIZATION FOR TEMPORARY OR PERMANENT DRAINAGE DITCHES OR SWALE SECTION WITH A CONTINUOUS SLOPE OF GREATER THAN 2 PERCENT.

THE CONTRACTOR SHALL ENSURE PIPE OUTLETS HAVE TEMPORARY OR PERMANENT ENERGY DISSIPATION WITHIN 24 HOURS OF CONNECTION TO A SURFACE WATER.

THE CONTRACTOR SHALL DIRECT DISCHARGES FROM BMPs TO VEGETATED AREAS TO INCREASE SEDIMENT REMOVAL AND MAXIMIZE STORMWATER INFILTRATION. VELOCITY DISSIPATION DEVICES MUST BE USED TO PREVENT EROSION WHEN DIRECTING STORMWATER TO VEGETATED AREAS.

SEDIMENT CONTROL MEASURES AND TIMING

THE CONTRACTOR IS RESPONSIBLE FOR ALL SEDIMENT CONTROL MEASURES FOR THE PROJECT.

SEDIMENT CONTROL MEASURES SHOWN ON PLANS ARE THE ABSOLUTE MINIMUM REQUIREMENTS. THE CONTRACTOR SHALL IMPLEMENT ADDITIONAL SEDIMENT CONTROL MEASURES AS NECESSARY TO PROPERLY MANAGE THE PROJECT AREA.

THE CONTRACTOR SHALL ENSURE SEDIMENT CONTROL MEASURES ARE ESTABLISHED ON ALL DOWN GRADIENT PERIMETERS BEFORE ANY UPGRADE/LAND DISTURBING ACTIVITIES BEGIN. THESE MEASURES SHALL REMAIN IN PLACE UNTIL FINAL STABILIZATION HAS BEEN ESTABLISHED.

A FLOATING SILT CURTAIN PLACED IN THE WATER IS NOT A SEDIMENT CONTROL BMP EXCEPT WHEN WORKING ON A SHORELINE OR BELOW THE WATERLINE. IMMEDIATELY AFTER THE SHORT TERM CONSTRUCTION ACTIVITY IS COMPLETE, PERMITTEE(S) MUST INSTALL AN UPLAND PERIMETER CONTROL PRACTICE IF EXPOSED SOILS STILL DRAIN TO A SURFACE WATER.

THE CONTRACTOR SHALL ENSURE SEDIMENT CONTROL PRACTICES REMOVED OR ADJUSTED FOR SHORT TERM ACTIVITIES BE RE-INSTALLED IMMEDIATELY AFTER THE SHORT TERM ACTIVITY HAS BEEN COMPLETED. SEDIMENT CONTROL PRACTICES MUST BE RE-INSTALLED BEFORE THE NEXT PRECIPITATION EVENT EVEN IF THE SHORT TERM ACTIVITY IS NOT COMPLETE.

THE CONTRACTOR SHALL ENSURE STORM DRAIN INLETS ARE PROTECTED BY APPROPRIATE BMPs DURING CONSTRUCTION UNTIL ALL SOURCES WITH POTENTIAL FOR DISCHARGING TO THE INLET HAVE BEEN STABILIZED.

THE CONTRACTOR SHALL PROVIDE SILT FENCE OR OTHER EFFECTIVE SEDIMENT CONTROL AT THE BASE OF THE STOCKPILES.

THE CONTRACTOR SHALL INSTALL PERIMETER CONTROL AROUND ALL STAGING AREAS, BORROW PITS, AND AREAS CONSIDERED ENVIRONMENTALLY SENSITIVE.

THE CONTRACTOR SHALL ENSURE VEHICLE TRACKING BE MINIMIZED WITH EFFECTIVE BMPs WHERE THE BMPs FAIL TO PREVENT SEDIMENT FROM TRACKING ONTO STREETS THE CONTRACTOR SHALL CONDUCT STREET SWEEPING TO REMOVE ALL TRACKED SEDIMENT.

THE CONTRACTOR SHALL IMPLEMENT CONSTRUCTION PRACTICES TO MINIMIZE SOIL COMPACTION.

THE CONTRACTOR SHALL ENSURE ALL CONSTRUCTION ACTIVITY REMAIN WITHIN PROJECT LIMITS AND THAT ALL IDENTIFIED RECEIVING WATER BUFFERS ARE MAINTAINED.

RECEIVING WATER	NATURAL BUFFER	IS THE BUFFER BEING ENCRoACHED ON?	REASON FOR BUFFER ENCRoACHMENT
M946-099.5 TROUT STREAM	50 FT	NO	NA
M946 TROUT STREAM	100 FT	NO	NA

A 50 FOOT NATURAL BUFFER MUST BE PRESERVED OR PROVIDE REDUNDANT (DOUBLE) PERIMETER SEDIMENT CONTROLS IF NATURAL BUFFER IS INFEASIBLE.

THE CONTRACTOR SHALL NOT UTILIZE SEDIMENT CONTROL CHEMICALS ON SITE.

INSPECTION AND MAINTENANCE
ALL INSPECTIONS, MAINTENANCE, REPAIRS, REPLACEMENTS, AND REMOVAL OF BMPs IS TO BE CONSIDERED INCIDENTAL TO THE BMP BID ITEMS.

THE PERMITTEE(S) IS RESPONSIBLE FOR COMPLETING SITE INSPECTIONS, AND BMP MAINTENANCE TO ENSURE COMPLIANCE WITH THE PERMIT REQUIREMENTS.

THE PERMITTEE(S) SHALL INSPECT THE CONSTRUCTION SITE ONCE EVERY 7 DAYS DURING ACTIVE CONSTRUCTION AND WITHIN 24 HOURS AFTER A RAINFALL EVENT GREATER THAN 0.5 INCHES IN 24 HOURS.

THE PERMITTEE(S) SHALL DOCUMENT A WRITTEN SUMMARY OF ALL INSPECTIONS AND MAINTENANCE ACTIVITIES CONDUCTED WITHIN 24 HOURS OF OCCURRENCE. RECORDS OF EACH ACTIVITY SHALL INCLUDE THE FOLLOWING:

- DATE AND TIME OF INSPECTIONS.
- NAME OF PERSON(S) CONDUCTING INSPECTION.
- FINDINGS AND RECOMMENDATIONS FOR CORRECTIVE ACTIONS IF NECESSARY.
- CORRECTIVE ACTIONS TAKEN.
- DATE AND AMOUNT OF RAINFALL EVENTS.
- POINTS OF DISCHARGE OBSERVED DURING INSPECTION AND DESCRIPTION OF THE DISCHARGE.
- AMENDMENTS MADE TO THE SWPPP.

THE PERMITTEE(S) SHALL SUBMIT A COPY OF THE WRITTEN INSPECTIONS TO THE ENGINEER AND OWNER ON A MONTHLY BASIS IF MONTHLY INSPECTION REPORTS ARE NOT SUBMITTED. MONTHLY PAYMENTS MAY BE HELD.

THE CONTRACTOR SHALL DOCUMENT AMENDMENTS TO THE SWPPP AS A RESULT OF INSPECTION(S) WITHIN 7 DAYS.

THE CONTRACTOR SHALL KEEP THE SWPPP, ALL INSPECTION REPORTS, AND AMENDMENTS ON SITE. THE CONTRACTOR SHALL DESIGNATE A SPECIFIC ON-SITE LOCATION TO KEEP THE RECORDS.

THE CONTRACTOR IS RESPONSIBLE FOR THE OPERATION AND MAINTENANCE OF TEMPORARY AND PERMANENT WATER QUALITY BMPs, AS WELL AS EROSION AND SEDIMENT CONTROL BMPs.

THE CONTRACTOR SHALL INSPECT EROSION PREVENTION AND SEDIMENTATION CONTROL BMPs TO ENSURE INTEGRITY AND EFFECTIVENESS. ALL NONFUNCTIONAL BMPs SHALL BE REPAIRED, REPLACED, OR SUPPLEMENTED WITH FUNCTIONAL BMPs WITHIN 24 HOURS OF FINDING. THE CONTRACTOR SHALL INVESTIGATE AND COMPLY WITH THE FOLLOWING INSPECTION AND MAINTENANCE REQUIREMENTS:

PERIMETER CONTROL DEVICES, INCLUDING SILT FENCE SHALL BE REPAIRED, OR REPLACED, WHEN THEY BECOME NONFUNCTIONAL. OR THE SEDIMENT REACHES 1/2 OF THE DEVICE HEIGHT. THESE REPAIRS SHALL BE MADE WITHIN 24 HOURS OF DISCOVERY.

TEMPORARY AND PERMANENT SEDIMENT BASINS SHALL BE DRAINED AND THE SEDIMENT REMOVED WHEN THE DEPTH OF SEDIMENT COLLECTED IN THE BASIN REACHES 1/2 THE STORAGE VOLUME. DRAINAGE AND REMOVAL MUST BE COMPLETED WITHIN 72 HOURS OF DISCOVERY.

SURFACE WATERS, INCLUDING DRAINAGE DITCHES AND CONVEYANCE SYSTEMS, MUST BE INSPECTED FOR EVIDENCE OF EROSION AND SEDIMENT DEPOSITION. THE CONTRACTOR SHALL REMOVE ALL DELTAS AND SEDIMENT DEPOSITED IN SURFACE WATERS, INCLUDING DRAINAGE WAYS, CATCH BASINS, AND OTHER DRAINAGE SYSTEMS. THE CONTRACTOR SHALL RE-STABILIZE THE AREAS WHERE SEDIMENT REMOVAL RESULTS IN EXPOSED SOIL. REMOVAL AND STABILIZATION MUST TAKE PLACE WITHIN 7 DAYS OF DISCOVERY, UNLESS PRECLUDED BY LEGAL, REGULATORY, OR PHYSICAL CONSTRAINTS. THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING ALL LOCAL, REGIONAL, STATE AND FEDERAL AUTHORITIES AND OBTAIN ANY APPLICABLE PERMITS, PRIOR TO CONDUCTING ANY WORK IN SURFACE WATERS.

CONSTRUCTION SITE VEHICLE EXIT LOCATIONS SHALL BE INSPECTED DAILY FOR EVIDENCE OF SEDIMENT TRACKING ONTO PAVED SURFACES. TRACKED SEDIMENT MUST BE REMOVED FROM ALL PAVED SURFACES WITHIN 24 HOURS OF DISCOVERY.

IF SEDIMENT ESCAPES THE CONSTRUCTION SITE, OFF-SITE ACCUMULATIONS OF SEDIMENT MUST BE REMOVED IN A MANNER AND AT A FREQUENCY SUFFICIENT TO MINIMIZE OFF-SITE IMPACTS.

EROSION PREVENTION BMP SUMMARY
SEE EROSION AND SEDIMENT CONTROL PLAN SHEET AND BID FORM FOR TYPE, LOCATION, AND QUANTITY OF EROSION PREVENTION BMPs.

SEDIMENT CONTROL BMP SUMMARY
SEE EROSION AND SEDIMENT CONTROL PLAN SHEETS AND BID FORM FOR TYPE, LOCATION, AND QUANTITY OF SEDIMENT CONTROL BMPs.

POLLUTION PREVENTION MANAGEMENT MEASURES

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL POLLUTION PREVENTION MANAGEMENT MEASURES.

ALL POLLUTION PREVENTION MEASURES ARE CONSIDERED INCIDENTAL TO THE MOBILIZATION BID ITEM, UNLESS OTHERWISE NOTED.

THE CONTRACTOR IS RESPONSIBLE FOR THE PROPER DISPOSAL, IN COMPLIANCE WITH MPICA DISPOSAL REQUIREMENTS, OF ALL HAZARDOUS MATERIALS, SOLID WASTE, AND PRODUCTS ON-SITE.

THE CONTRACTOR SHALL ENSURE BUILDING PRODUCTS THAT HAVE THE POTENTIAL TO LEAK POLLUTANTS ARE KEPT UNDER COVER TO PREVENT THE DISCHARGE OF POLLUTANTS.

THE CONTRACTOR SHALL ENSURE PESTICIDES, HERBICIDES, INSECTICIDES, FERTILIZERS, TREATMENT CHEMICALS, AND LANDSCAPE MATERIALS ARE COVERED TO PREVENT THE DISCHARGE OF POLLUTANTS.

THE CONTRACTOR SHALL ENSURE HAZARDOUS MATERIALS AND TOXIC WASTE IS PROPERLY STORED IN SEALED CONTAINERS TO PREVENT SPILLS, LEAKS, OR OTHER DISCHARGE. STORAGE AND DISPOSAL OF HAZARDOUS WASTE OR HAZARDOUS MATERIALS MUST BE IN COMPLIANCE WITH MINN. R. CH. 7045 INCLUDING SECONDARY CONTAINMENT AS APPLICABLE.

THE CONTRACTOR SHALL ENSURE ASPHALT SUBSTANCES USED ON-SITE SHALL ARE APPLIED IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS.

THE CONTRACTOR SHALL ENSURE PAINT CONTAINERS AND CURING COMPOUNDS SHALL BE TIGHTLY SEALED AND STORED WHEN NOT REQUIRED FOR USE. EXCESS PAINT AND/OR CURING COMPOUNDS SHALL NOT BE DISCHARGED INTO THE STORM SEWER SYSTEM AND SHALL BE PROPERLY DISPOSED OF ACCORDING TO MANUFACTURER'S INSTRUCTION.

THE CONTRACTOR SHALL ENSURE SOLID WASTE BE STORED, COLLECTED AND DISPOSED OF PROPERLY IN COMPLIANCE WITH MINN. R. CH. 7035.

THE CONTRACTOR SHALL ENSURE POTABLE TOILETS ARE POSITIONED SO THAT THEY ARE SECURE AND WILL NOT BE TIPPED OR KNOCKED OVER. SANITARY WASTE MUST BE DISPOSED OF PROPERLY IN ACCORDANCE WITH MINN. R. CH. 7041.

THE CONTRACTOR SHALL MONITOR ALL VEHICLES ON-SITE FOR LEAKS AND RECEIVE REGULAR PREVENTION MAINTENANCE TO REDUCE THE CHANCE OF LEAKAGE.

THE CONTRACTOR SHALL ENSURE WASHOUT WASTE MUST CONTACT THE GROUND AND BE PROPERLY DISPOSED OF IN COMPLIANCE WITH MPICA RULES.

THE CONTRACTOR SHALL INCLUDE SPILL KITS WITH ALL FUELING SOURCES AND MAINTENANCE ACTIVITIES. SECONDARY CONTAINMENT MEASURES SHALL BE INSTALLED AND MAINTAINED BY THE CONTRACTOR.

THE CONTRACTOR SHALL ENSURE SPILLS ARE CONTAINED AND CLEANED UP IMMEDIATELY UPON DISCOVERY. SPILLS LARGE ENOUGH TO REACH THE STORM WATER CONVEYANCE SYSTEM SHALL BE REPORTED TO THE MINNESOTA DUTY OFFICER AT 1.800.422.0788.

PERMIT TERMINATION CONDITIONS

THE CONTRACTOR IS RESPONSIBLE FOR ENSURING FINAL STABILIZATION OF THE ENTIRE SITE. PERMIT TERMINATION CONDITIONS INCLUDE BUT ARE NOT LIMITED TO THE FOLLOWING:

ALL SOIL DISTURBING ACTIVITIES HAVE BEEN COMPLETED.

ALL EXPOSED SOILS HAVE BEEN UNIFORMLY STABILIZED WITH AT LEAST 70% VEGETATION COVERAGE.

PERMANENT STORM WATER MANAGEMENT SYSTEM(S) ARE CONSTRUCTED AND ARE OPERATING AS DESIGNED.

ALL DRAINAGE DITCHES, PONDS, AND ALL STORM WATER CONVEYANCE SYSTEMS HAVE BEEN CLEARED OF SEDIMENT AND STABILIZED WITH PERMANENT COVER TO PRECLUDE EROSION.

ALL TEMPORARY SYNTHETIC BMPs HAVE BEEN REMOVED AND PROPERLY DISPOSED OF.

IN RESIDENTIAL CONSTRUCTION, INDIVIDUAL LOTS ARE CONSIDERED FINALLY STABILIZED IF THE STRUCTURE(S) ARE FINISHED AND TEMPORARY EROSION PROTECTION AND DOWNGRADIENT PERIMETER CONTROL HAS BEEN COMPLETED, THE RESIDENCE HAS BEEN SOLD TO THE HOMEOWNER, AND THE HOMEOWNER HAS BEEN PROVIDED A "HOMEOWNER FACT SHEET" BY THE CONTRACTOR.

AGRICULTURAL LAND DISTURBED HAS BEEN RETURNED TO ITS PRECONSTRUCTION AGRICULTURAL USE.

Rev. 01/2023, SEH Project 107247, Revision Issue Description, Date, Rev #, Revision Issue Description, Date, SEH Project 107247, Revision Issue Description, Date, Rev #, Revision Issue Description, Date

SEH Project	107247	Rev #	Revision Issue Description	Date	Rev #	Revision Issue Description	Date
Drawn By	HP						
Designed By	HS						
Checked By	JW						









I HEREBY CERTIFY THAT THE PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED LICENSE PROFESSIONAL UNDER THE LAWS OF THE STATE OF MINNESOTA.
John Wegman
 JOHN WEGMAN, P.E.
 DATE: 7/26/23 LICENSE NO: 43331







NEAL STREET RAVINE STABILIZATION
 RED WING, MINNESOTA

SWPPP







Save: 26/02/2025 9:58 AM Expedient - Proj: 26/02/2025 10:16 AM X:\P\RD\RD\WKS\107247\247-Subs-augr-01-drawings\10-Construct\dwg\sheet\001\07247.dwg









Save: 2/6/2025 9:58 AM Expedition Plot: 2/6/2025 10:16 AM X:\P\RAWING\1672475-Sub-stg-51-drawings\10-Construct\dwg\sheet17of28.dwg









Save: 20/02/2023 10:55 AM Expedition: Proj: 26/2023 10:16 AM X:\PT\ROWING\167247\Scheme\stage1\Drawings\10-Construction\stage1\167247.dwg









Save: 20/02/2025 10:58 AM Expedition: Proj: 28/2023 10 10 AM X: FT RWING 1072475 Scheme: sgr-51 drawings: 10: Civil and drainage: 00192272.dwg









Save: 26/02/2025 10:55 AM Expedition - Proj: 26/2023 10 16 AM X: FT RW RWING 1072475 - Scheme - Stage 5 - Drawings 10 - Civil - Any - Sheet 0019227X.dwg









Save: 20/02/2025 10:58 AM Expedition Plot: 20/02/2025 10:18 AM X:\P\RAWING\1072475-Subsidiary-51-drawings\10-Construction\sheet\01\0227X.dwg



Save: 2025/05/15 08:41:00 AM - E:\Projects\2025\25+50 - Neal Street Ravine\Drawings\25+50 - Neal Street Ravine\Drawings\25+50 - Neal Street Ravine.dwg



Save: 2025/05/15 08:58 AM Expedition - Proj: 282023 - 15177 AMX - FT ROWING 10172475 - Schemat - Stage: 5 - Drawings: 10 - Content: any plan view (01) 27+25.dwg



Save: 2/6/2025 9:55 AM Expedient Plot: 2/6/2025 10:17 AM X:\P\RAWING\1072475-Sub-A-1.dgn: E1: Drawing: 10: Civil: dmyr.dwg: \$V:\P\2475.dwg

